

2 1-00024

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 155-21,059 - 0000  
SWSWNE, SEC. 32, T. 7 S, R. 8 W/E  
2970 feet from N/S section line  
2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9427

Lease Name Welker Well # A #1

Operator: Sharp Engineering

County Reno 120.25

Name & Address 708 One Main Place

Well Total Depth 3700 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis License Number 5420

Address Great Bend, KS

Company to plug at: Hour: P.m. Day: 18 Month: 6 Year: 19 85

Plugging proposal received from \_\_\_\_\_

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: 35 sacks of cement at 1100 feet; 35 sacks of cement at 60 feet  
on wood and rubber plug; 10 sacks of cement in rat hole;  
60/40 pos, 6% gel

Plugging Proposal Received by Stan Marcotte  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:00a. Day: 19 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT Filled hole with heavy mud. Ran drill pipe to  
1100 feet and spotted 35 sacks of cement. Pulled drill pipe to  
370 feet and spotted 35 sacks of cement. Pulled drill pipe to 60  
feet, spotted 25 sacks of cement on top of wood and rubber plug.  
Ran one joint of drill pipe in rat hole and spotted 10 sacks  
cement to surface. 60/40 pos. 6% gel

Remarks: Howco #085347-9 (If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
6-25-85  
JUN 25 1985

CONSERVATION DIVISION  
Wichita, Kansas

Signed J.C. Sander  
(TECHNICIAN)

INVOICED

DATE 6-25-85 WK

INV. NO. 8704