

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20, 707, 0000

Sec. 5, T 26 S, R 16 W

NE, NE, NE 1/4 feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Mayhew Well # 1

Operator: Oil Producers Inc
Name & Address of Kansas

County Edwards

Box 39A, Rt # 1
Hamiland, KS 67059

Well Total Depth 4505 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 444

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 2:00pm Day: 21 Month: MARCH Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bob Brenneman

(company name) Kelso (phone)

were: use 50/50 foz mix, 2% gel, 3% cc - packer was set @ 4394, perfs @ 4383. Gas pumped off and 15 1/2 cmt put on packer to 4316. Rec 2513' 7 1/2 and pump 3 x hells, 15 x gel, 70 x cmt, 10 x gel, 10 x hells, release plug and follow w/ 100 x cmt.

Signed R. Barlutton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:45pm Day: 21 Month: March Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered. Cementing by Allied. May, pump press. @ 500#, shut in press. 300#

Remarks: 7 1/2" @ 4504.

Mr. Steve Durrant observed plugging.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION Signed R. Barlutton (TECHNICIAN)

INVOICED DATE 3-30-83 INV. NO. 3860-4

MAR 23 1983 CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 9-82