

To: 1 041237 3-19  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-047-21,022-000  
NW SE NE, SEC. 5, T. 26 S, R. 16 W XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061  
Operator: Oil Producers, Inc. of Kansas  
Name:  
Address P.O. Box 8647  
Wichita, KS 67208

3847 feet from S section line  
855 feet from E section line  
Lease Name Sharp Well # 1  
County Edwards 149.01  
Well Total Depth 4585 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 12:30 p.m. Day: 19 Month: 3 Year: 19 97

Plugging proposal received from Kent Strube  
(company name) D S & W Well Servicing, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4584' w/175 sx cement, Perfs at 4508-12'

1st plug sand back to 4450' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release  
wiper plug and pump 150 sx cement.

3-26-97

RECEIVED  
KANSAS CORP COMM  
MAR 26 1997

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 19 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Maximum pressure 100 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-26-97

INV. NO. 47822

3-19

Signed Stephen J. Pfeifer (TECHNICIAN)