

061146

10-20-88

API NUMBER 15- 047-20,481-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C N/2 NE, SEC. 8, T 26 S, R 16 W/EX

4620 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Martin Well # 1

Operator: Oil Producers Inc. of Kansas

County Edwards 144.76

Name & Address Box 8647

Well Total Depth 4454 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 415

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 20 Month: 10 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4506' Perfs at 4410-14, 4420-26, 4434-40'

1st plug sand back to 4360' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

OCT 24 1988

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: AT Wichita, Kansas Part None

Operations Completed: Hour: 10:15 a.m. Day: 20 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4360' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 300 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1969' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-28-88

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 22835