

12-8-87 15-047-20659-0000

API NUMBER 15-Drill completion date 5/19/80

1 061045  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NE SW, SEC. 8, T 26 S, R 16 W/E  
1650 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992  
Operator: Patton Oil Company  
Name & Address: 672 West 4th Street  
Hoisington, KS 67544

Lease Name Welsch Well # 2  
County Edwards 145.11  
Well Total Depth 4465 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 498

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:45 p.m. Day: 8 Month: 12 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4462' PRTD 4467' Open hole from 4462-4467'  
1st plug sand back to 4410' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:20 p.m. Day: 8 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4410' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

12-11-87  
RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2410' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this report.)

INVOICED  
(If additional description is necessary, use BACK of this report.) observe this plugging.

Signed Paula Luttig (TECHNICIAN)

DATE 12-14-87  
INV. NO. 19265