

1060893

163
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Operator: Oil Producers Inc. of Kansas
Name & Address Box 8647
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:15 a.m. Day: 28 Month: 10 Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4559' Perfs at 4487-4502' PBD 4528' Elevation 2088'GL

1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 28 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 4 sx cement on top of sand
through bailer.

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

released rubber plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Recovered 2500' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

10-31-86
OCT 31 1986

INVOICED

observe this plugging.

DATE 11-3-86

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 15280