

1 090028

11-13

API NUMBER 15- 047-20,419- 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NE, SEC. 9, T 26 S, R 16 W/E

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Schultz Well # 1

Operator: Patton Oil Company

County Edwards 142.90

Name & Address 672 W. 4th St.

Well Total Depth 4397 feet

Hoisington, KS 67544

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 408

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 13 Month: 11 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4394' w/125 sx cement, Open hole from 4394-4409'

1st plug sand back to 4344' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 13 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4394' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 0.

RECEIVED STATE CORPORATION COMMISSION NOV 15 1990

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing

(if additional description is necessary, use BACK of this form.)

INVOICED (if field representative observe this plugging.)

Signed [Signature] (TECHNICIAN)

DATE 11-19-90

INV. NO. 29993