

1 050991

1-25-88

API NUMBER 15- 047-20,473 -0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE NE, SEC. 9, T 26 S, R 16 W/E
4290 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Schultz Well # 3

Operator: Patton Oil Company

County Edwards 145.24

Name & Address 672 West 4th Street

Well Total Depth 4469 feet

Hoisington, KS 67544

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 423

Abandoned Oil Well X Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:50 a.m. Day: 25 Month: 1 Year: 19 88

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4465' PBD 4450' Perfs at 4410-38'

1st plug sand back to 4360' with 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12 p.m. Day: 25 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4360' and dumped 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION 1-27-88 JAN 27 1988

Maximum pressure 100 psi and shut in 25 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2321' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED
DATE 1-28-88
WV. NO. 19694

Signed Richard W. Lacey (TECHNICIAN)