

12-22-87 15-047-20570-0000

To: 1 061052
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 11/30/79

NE NE NW, SEC. 9, T 26 S, R 16 W/EX

4950 feet from S section line

2970 feet from E section line

Lease Name Michael Well # 1

County Edwards 144.56

Well Total Depth 4448 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 466

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Operator: Patton Oil Company

Name & Address 672 West 4th Street

Hoisington, KS 67544

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 22 Month: 12 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4440' PBDT 4430' Perfs 4405' (top)

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 120 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 22 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of

sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 120 sx cement.

Maximum pressure 250 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2351' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOLVED

DATE 1-7-88

INV. NO. 19401

Signed Paul A. Luthi (TECHNICIAN)