

1 120334

10-30

333

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA 15-047-20612-0000 R

NE NE SE, SEC. 9, T 26 S, R 16 W/R

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Gallup Well # 1-X

Operator: Benson Mineral Group, Inc.

County Edwards 148.04

Name:

Address 1536 Cole Blvd., Suite 220

Well Total Depth 4555 feet

Golden, CO 80401

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 30 Month: 10 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4523' PBTB 4501' Perfs at 4420-54'

1st plug sand back to 4370' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
11-6-89
NOV - 6 1989

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 30 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4380' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-100 psi and shut in 0 psi-not on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (do not stamp) observe this plugging.

Signed Steve Pfeifer
(TECHNICIAN)

DATE 11-7-89

INV. NO. 26368