

1061051

12-22-87 15-047-20657-0000

API NUMBER 15-Drill Completion Date 6/27/80

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NW, SEC. 9, T 26 S, R 16 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Michael Well # 3

Operator: Patton Oil Company
Name & Address: 672 West 4th Street
Hoisington, KS 67544

County Edwards 146.41
Well Total Depth 4505 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 457

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 a.m. Day: 22 Month: 12 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-928-2457

were: 5 1/2" at 4503' PBD 4412' Perf 4401' (top)
1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 22 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 120 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2429' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

STATE OF KANSAS RECEIVED
12-29-87
DEC 29 1987
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

Observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 1-7-88

INV. NO. 19402