

To: 1 090027
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-13
API NUMBER 15- 047-20,658-0000

NE NW SW, SEC. 9, T 26 S, R 16 WEX

2310 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lessee Name Welsch Well # 1

Operator: Patton Oil Company

County Edwards 144.59

Name & Address 672 W. 4th St.

Well Total Depth 4449 feet

Hoisington, KS 67544

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 461

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 13 Month: 11 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4447' w/150 sx cement, Open hole from 4447-4460'

1st plug sand back to 4400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:45 p. Day: 13 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 300 psi and shut in 100 psi.

NOV 15 1990 11-1590

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2230' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

NOV 20 1990

DATE

INV. NO. 30017

Signed (TECHNICIAN)