

1 090029

11-13

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 047-20,660-6000

NE SE NE, SEC. 9, T 26 S, R 16 W/E
3630 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Schultz Well # 5

Operator: Patton Oil Company

County Edwards 143.84

Name & Address 672 W. 4th St.

Well Total Depth 4426 feet

Hoisington, KS 67544

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 440

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 13 Month: 11 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4422' w/150 sx cement, Open hole from 4422-32'

1st plug sand back to 4370' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs., 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:20 p.m. Day: 13 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4422' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement. Went on vacuum.

RECEIVED STATE CORPORATION COMMISSION

Returned at 2:05 p.m. on 11/13/90. 3rd plug mixed 2 sx cc w/40 sx cement.

11-15-90 NOV 15 1990

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing.

CONSERVATION DIVISION Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED (with check) observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 11-19-90

INV. NO. 29992