

1 050992

1-25-88

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,661-6000

SW SE NE, SEC. 9, T 26 S, R 16 N/E

2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Schultz Well # 6

Operator: Patton Oil Company

County Edwards 144.72

Name & Address 672 West 4th Street

Well Total Depth 4453 feet

Hoisington, KS 67544

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 436

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 25 Month: 1 Year: 19 88

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4443' Open hole at 4443-53' Perfs at 4401-21'

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 25 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 100 psi and shut in 25 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
1-27-88
JAN 27 1988

CONSERVATION DIVISION
Wichita, Kansas

INVOICED ~~XXXXXX~~ observe this plugging.

Signed Richard M. Lacey (TECHNICIAN)

DATE 1-28-88

INV. NO. 191093