

1 090363

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,725-00-00 *R*

NE SW SE, SEC. 9, T 26 S, R 16 W/X

990 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Atteburry "B" Well # 1-9

Operator: Benson Mineral Group, Inc.

County Edwards 158.55

Name & Address 1536 Cole Blvd., Suite 220

Well Total Depth 4530 feet

Golden, CO 80401

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 4.15

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 pm Day: 18 Month: June Year: 19 85

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4350' Perfs at 4419-25'

1st plug sand back to 4370' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:40 pm Day: 18 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150

sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
6-21-85  
JUN 21 1985

Maximum pressure 500 psi and shut in 200 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' 4 1/2" casing DIVISION  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-26-85

INV. NO. 8714

Signed Robert Brachuttan (TECHNICIAN)