

1 120333

10-30

334
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,775 -0000

NE NW SE, SEC. 9, T 26 S, R 16 W/E

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Gallup Well # 2-9

Operator: Benson Mineral Group, Inc.

County Edwards 147.39

Name & Address 1536 Cole Blvd., Suite 220

Well Total Depth 4535 feet

Golden, CO 80401

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 490

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 30 Month: 10 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 4527' PBTD 4498' Perfs at 4424-26, 4430-52, 4384-4404'

1st plug sand casing back to 4354' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
11-6-89
NOV - 6 1989
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Pfeifer

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 30 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4354' and dumped 4 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-100 psi and shut in 0 psi-not on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

Signed Quand Runko
(TECHNICIAN)

DATE 11-7-89

INV. NO. 26369