

11-21

To: 1 120166
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-047-21,261-0000
SW SW NW, SEC. 9, T 26 S, R 16 W/8

TECHNICIAN'S PLUGGING REPORT

11-29-88

2970 feet from S section line
4950 feet from E section line

Operator License # 5992
Operator: Patton Oil Company
Name & Address: 672 West 4th
Hoisington, KS 67544

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1988
CONSERVATION DIVISION
Wichita, Kansas

Lease Name: Michael Well # 4
County: Edwards 146.25
Well Total Depth: 4500 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 478
Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____
Plugging Contractor: Pratt Well Service, Inc. License Number 5893
Address: P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 21 Month: 11 Year: 19 88

Plugging proposal received from Bill Reed
(company name) Patton Oil Company (phone) 316-653-2277
were: 5 1/2" at 4498' PBD 4092' Perfs at 4062-68'

1st plug sand back to 4000' and dump 5 sx cement on top of sand through bailer.
2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12 p.m. Day: 21 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4000' and dumped 5 sx cement.
on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-200 psi and shut in 0 psi (not on vacuum).

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2267' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE DEC 1 1988
INV. NO. 22212

Signed Duane Rankin (TECHNICIAN)