

MAR 31 1989 15-047-00043-294 R
API NUMBER 15- Drill Completion Date 5/8/56

To: 1 040258
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SE, SEC. 10, T 26 S, R 16 (W) @
2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9449
Operator: Great Eastern Energy & Development Corporation
Name & Address: 672 West 4th Street
Hoisington, KS 67544

Lease Name Gibson Well # 5
County Edwards 154.54
Well Total Depth 4755 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 p.m. Day: 31 Month: 3 Year: 19 89

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4752' Perfs at 4392-4412'
1st plug sand back to 4340' and dump 5 sx cement top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1989
CONSERVATION DIVISION
Wichita, Kansas

4-4-89

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 31 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4340' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

INVOICED
DATE 4-19-89
INV. NO. 24331