

1 120513

12-2715-047-10070-00-01 279 R

API NUMBER 15- Washed down 1/24/79

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SW NW, SEC. 10, T 26 S, R 16 W/E

3300 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8791

Lease Name Schultz Well # A-4 OWWO

Operator: El-Kan Exploration

County Edwards 147.71

Name & Address P.O. Box 105

Well Total Depth 4545 feet

Garfield, KS 67529

Conductor Pipe: Size feet

Surface Casing: Size 8 feet 278

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Greensburg Well Service License Number 5414

Address 303 E. Kansas, Greensburg, KS 67054

Company to plug at: Hour: 3 p.m. Day: 27 Month: 12 Year: 19 90

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

were: 5 1/2" at 4541', Perfs at 4480-4502'

1st plug sand back to 4430' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel,  
100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All C Part None

Operations Completed: Hour: 4 p.m. Day: 27 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4430' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

No pressure. Shut in on a slight vacuum.

RECEIVED  
STATE CORPORATION COMMISSION  
1-4-91  
JAN 4 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1542' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If possible, please observe this plugging.)

DATE 1-22-91

Signed Duane Rankin (TECHNICIAN)

INV. NO. 30546

12-27