

120515

12-27

280

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,287 -00-00

NE NE NW, SEC. 10, T 26 S, R 16 W/E

4950 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8791

Lease Name Schultz Well # 1 A

Operator: El-Kan Exploration

County Edwards 147.38

Name & Address P.O. Box 105

Well Total Depth 4535 feet

Garfield, KS 67529

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Greensburg Well Service License Number 5414

Address 303 E. Kansas, Greensburg, KS 67054

Company to plug at: Hour: 5:30 p.m. Day: 27 Month: 12 Year: 19 90

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

were: 5 1/2" at 4430', Perfs at 4384-4404'

1st plug sand back to 4330' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel,

100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:30 p.m. Day: 27 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 200 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3410' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (If you wish to observe this plugging.)

DATE JAN 22 1991

Signed Duane Rankin (TECHNICIAN)

INV. NO. 30547 12-27