

To: 1 040259  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9449  
Operator: Great Eastern Energy & Development  
Name & Corporation  
Address 672 West 4th Street  
Hoisington, KS 67544

MAR 31 1989 15-047-20314-293  
API NUMBER 15-Drill Completion Date 3/2/78  
C SW NE, SEC. 10, T 26 S, R 16 W/E  
3300 feet from S section line  
1980 feet from E section line  
Lease Name Gibson Well # 2  
County Edwards 145.60  
Well Total Depth 4480 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 461

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 31 Month: 3 Year: 19 89

Plugging proposal received from Millard Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4480' Perfs at 4385-98'

1st plug sand back to 4330' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper pump 125 sx cement.

4-4-89  
Plugging Proposal Received by James R. Kapp  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11:30 a.m. Day: 31 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 5 sx cement on top of  
sand through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
DATE 4-19-89  
INV. NO. 24330

Signed Stephen J. Pfeifer  
(TECHNICIAN)