

To: 1 120516
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-27
API NUMBER 15- 047-20,359-0000
N/2 N/2 NW, SEC. 10, T 26 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8791
Operator: El-Kan Exploration
Name & Address: P.O. Box 105
Garfield, KS 67529

4950 feet from S section line
3960 feet from E section line
Lease Name Schultz Well # 2 A
County Edwards 146.02
Well Total Depth 4493 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7" feet 426

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number 5414
Address 303 E. Kansas, Greensburg, KS 67054

Company to plug at: Hour: 11 a.m. Day: 27 Month: 12 Year: 19 90

Plugging proposal received from Carl Schield
(company name) Greensburg Well Service (phone) 316-723-2204

were: 5 1/2" at 4493', Perfs at 4389-4401'
1st plug sand back to 4340' and dump 5 sx cement on top of sand through bailer
2nd plug pump 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 7" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 27 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4340' and dumped 5 sx cement on top of
sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 7" wiper plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2380' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED (if desired, observe this plugging.)

Signed Duane Rankin
(TECHNICIAN)

DATE JAN 22 1991

INV. NO. 30548

12-27