

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

*Rec'd  
11-21-85*

*6/86*

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-081-20333-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

EASE OPERATOR Amoco Production Company OPERATORS LICENSE NO. 5952

ADDRESS P. O. Box 432 Liberal, KS 67901 PHONE # (316) 624-6241

EASE (FARM) Ellsaesser "A" WELL NO. 1 WELL LOCATION C SE $\frac{1}{4}$  SE $\frac{1}{4}$  COUNTY Haskell

SEC. 22 TWP. 29S RGE. 33  or  TOTAL DEPTH 5550 PLUG BACK TD 5200

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 9-5/8" SET AT 1670' CEMENTED WITH 1005 SACKS

CASING SIZE 7" SET AT 5550' CEMENTED WITH 370 SACKS

PERFORATED AT 5322-5327' 5360-5374

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL See back side

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8:00 a.m. 12-2-85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Richard Jenisch PHONE # (316) 649-2303

ADDRESS P. O. Box 697 Satanta, KS 67870

PLUGGING CONTRACTOR To be bid LICENSE NO. \_\_\_\_\_

ADDRESS \_\_\_\_\_ PHONE # ( ) \_\_\_\_\_

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: *R. L. Hiatt* R. L. Hiatt  
(Operator or Agent)

DATE: 11-21-85

*(1)*



Amoco Production Company

November 11, 1985

File: RAR-935-400.1

Recommended Plugging Procedure  
Ellsaesser "A" No. 1  
Sec. 22-T29S-R33W  
Haskell County, Kansas

Listed below is the recommended procedure to plug and abandon the subject wellbore.

1. Set a CIBP at 4150' and cap with 2 sacks of cement.
2. Locate the casing free point and cut casing off (top of cement is at approximately 3400').
3. Load hole with mud from CIBP to 50' below casing cut point.
4. Set a cement plug from 50' below to 50' above the casing stub.
5. Load hole with mud from cement plug to 3100'.
6. Set a cement plug across the Hugoton and Council Grove from 3100' to 2500'.
7. Load hole with mud from 2500' to 1700'.
8. Set a cement plug from 1570' to 1700'.
9. Load hole with mud from 1570' to 40' below grade.
10. Set a cement plug from 5' to 40'.
11. Cut casing off 5' below grade, weld on a steel cap with proper identification and back fill the well site.

All cement used should be Class "H" cement and the mud will be 9.5 ppg and have a viscosity of 36 cp.

C. H. Kelm

BKB/df

RECEIVED  
STATE CORPORATION COMMISSION

NOV 25 1985

CONSERVATION DIVISION  
Wichita, Kansas



WIN CARLIN  
JHAEL LENNEN  
RGALEE WRIGHT  
TH R. HENLEY  
JITH A. McCONNELL  
AN J. MCLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

### THIS NOTICE

FEB 26 1986

EXPIRES

November 26, 1985  
WELL PLUGGING NOTICE

Ellsaesser "A" #1  
C SE/4 SE/4  
Sec. 22-29S-33W  
Haskell County

Amoco Production Company  
P. O. Box 432  
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of William R. Bryson in cursive.

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to  
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).