

15-047-10141-0006

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Edwards County. Sec. 5 Twp. 26 Rge. 16 (X) (W)

Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner L. C. Smitherman - Oil Producer
Lease Name Mathis Well No. 1
Office Address Box 627 - Augusta, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 14 1958
Application for plugging filed June 14 1958
Application for plugging approved June 14 1958
Plugging commenced June 14 1958
Plugging completed June 14 1958
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4541 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Pipe			8 5/8"	403'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug 240' cemented with 20 sacks cement - Mud to 30' -
Plug set at 30' - Cemented 10 sacks cement on top
Job completed 10 P.M., June 14, 1958.

6-19-1958
RECEIVED
STAT. CORP. COM.
JUN 19 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. C. Smitherman Drilling Co.
Address Box 627 - Augusta, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
Carl J. Lehr (employee of owner) or (owner/agent) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl J. Lehr
Box 627 - Augusta, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of June, 1958

My commission expires January 28, 1961

Shirley Ann Jackson
Shirley Ann Jackson Notary Public.

PLUGGING
FILE SEC. 5 T. 26 R. 16W
BOOK PAGE 109 LINE 19

15-647-10141-0000

MATHIS #1

COMPANY: L. C. Smitherman - Oil Producer
CONTRACTOR: L. C. Smitherman Drilling Co.

Location: SE SE SW, Sec. 5-26-16,
Edwards Co., Kansas
Elevation: 2090 DF
Casing: 414* 8 5/8" cemented W/250 sks.

Commenced: May 24, 1958
Completed: June 14, 1958

FIGURES INDICATE BOTTOMS OF FORMATIONS:

0	200	Sand
200	410	Sand & Shale
410	1100	Red Bed & Shale
1100	1800	Shale
1800	2190	Shale & Lime
2190	2260	Lime - Ft. Riley
2260	3446	Lime & Shale
3446	3502	Shale
3502	3704	Lime & Shale
3704	3769	Lime
3769	3925	Lime & Shale
3925	3953	Brown Lime
3953	4002	Lime
4002	4048	Lime & Shale
4048	4126	Lime
4126	4205	Lime & Shale
4205	4295	Lime
4295	4327	Lime & Shale
4327	4415	Lime
4415	4455	Lime & Shale
4455	4585	Lime
4585	4541	Chert & Lime
4541		TOTAL DEPTH

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Mathis #1 located in the SE SE SW, Section 5-26-16, Edwards County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY

Carl J. Lehr
Carl J. Lehr

Subscribed and sworn to before me this 17th day of June, 1958.

Shirley Ann Jackson
(Notary Public)

My Commission expires January 28, 1961.

PLUGGING	
FILE	SEC. 5 T. 26 R. 16W
BOOK	PAGE 109 LINE 19