

15-047-20707-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Edwards SEC. 5 TWP. 26s RGE. 16w E/W  
 Location as in quarters or footage from lines:  
NE NE NE


Lease Owner Oil Producers Inc, of Kansas  
 Lease Name Mayhew #1 Well No. \_\_\_\_\_  
 Office Address Box 8647, Wichita, Ks. 67208  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 3/4/83  
 Plugging completed 3/21/83  
 Reason for abandonment of well or producing formation \_\_\_\_\_  
Depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4505'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	440'	none
				4 1/2"	4504'	2486'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Pumped bottom with 15 sacks cement & 1 hull to 4300'. Shot well at 3016',  
 2810', 2612', & 2509'. Pulled total of 62 joints. Plugged well with 3 hulls,  
 15 gel, 70 cement, 10 gel, 1 hull, plug, & 110 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March, 19 83

My Commission expires:



Irene Hoover  
 Notary Public.  
 STATE CORPORATION COMMISSION

APR 01 1983

CONSERVATION DIVISION  
 Wichita, Kansas