

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

15-047-20964-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 5 TWP. 26S RGE. 16W E/W
Location as in quarters or footage from lines:
SW SW SW

Lease Owner F. G. Holl
Lease Name Bradley-Mathes #1-5 Well No. 1-5
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed November 25, 1981
Application for plugging filed November 25, 1981
Plugging commenced 4:00 PM, November 25, 1981
Plugging completed 6:40 PM, November 25, 1981
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Darrant

Producing formation _____ Depth to top _____ bottom _____ T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	430'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud,
Pumped through open ended drill pipe 70 sacks
50/50 Pozmix with 4% gel and 3% cc at 780';
40 sacks at 390'; Bridge with 1/2 sack hulls, plug
and 10 sacks at 40'; 10 sacks in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579


STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas
(Address) 67579

SUBSCRIBED AND SWORN TO before me this 30th day of November, 1981.

My Commission expires: _____



[Signature]
Agnes, D. Wurst, Notary Public.

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

15-047-20964-0000

WELL LOG - - - - - BRADLEY-MATHES #1-5
Located: SW SW SW, Section 5-26S-16W, Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 19, 1981
COMPLETED: November 25, 1981

TOTAL DEPTH: 4630'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 220 Sand and Surface Soil	Ran 11 joints new 8 5/8", 24# casing.
220 - 433 Shale	417.88' pipe set at 430' K.B. Cemented
433 - 525 Shale, Sand, Red Bed	with 325 sacks 60/40 Pozmix with 3% cc.
525 - 1123 Shale	Plug down at 9:45 PM, 11-19-81, by Howco.
1123 - 1139 Anhydrite	
1139 - 1635 Shale, Lime Stringer	
1625 - 4630 Lime and Shale	Plugged.

Deviation Surveys: 1 1/8° at 2256'
1° at 4490'