

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

15-047-21072-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Edwards SEC. 7 TWP. 26S RGE. 16 E/W  
 Location as in quarters or footage from lines:  
C SW SW


Lease Owner Vincent Oil Corporation  
 Lease Name Shannon Well No. #1  
 Office Address 125 N. Market, Suite 1110 Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry  
 Date Well Completed 11-7-82  
 Application for plugging filed 11-7-82  
 Plugging commenced 11-7-82  
 Plugging completed 11-7-82  
 Reason for abandonment of well or producing formation 1

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4547'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	471'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

- Spotted 70 sx. cement @ 1100' thur drillpipe.
- Spotted 40 sx. cement @ 460' thur drillpipe.
- Solid bridge plug @ 40', Spotted 10 sx. cement thur drillpipe.
- Spotted 10 sx. cement in rathole.
- Spotted 5 sx. cement in water well.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor White & Ellis Drilling, Inc.  
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Ernest Sifford (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) *Ernest Sifford*  
401 E. Douglas #500 Wichita,  
 (Address) Ks. 67202


SUBSCRIBED AND SWORN TO before me this 2nd day of December 1982

My Commission expires:



Carolyn J. Tjaden  
 Notary Public.  
 STATE OF KANSAS

DEC 3 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas



15-047-21072-0000

# WHITE

AND ELLIS DRILLING, Inc.

## DRILLERS LOG

OPERATOR: Vincent Oil Corporation 125 N. Market - Suite 1110 Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,  
Wichita, Ks. 67202

Lease Name Shannon Well No. #1

Sec. 7 T. 26S R. 16W Spot C SW SW

County Edwards State Kansas Elevation \_\_\_\_\_

### Casing Record:

Surface: 8 5/8" @ 471' with 300 sx. 2%gel  
3%cc

Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ sx.

Type Well: D & A Total Depth 4547'

Drilling Commenced 10-29-82 Drilling Completed 11-7-82

Formation	From	To	Tops
Cellar	0	7	Heebner 3798
Sand, Clay Shale	7	1933	Mississippi 4488
Lime, Shale	1933	3798	Kinderhook 4510
Shale	3798	3960	
Lime, Shale	3960	4488	
Lime	4488	4510	
Shale	4510	4547	

RECEIVED  
STATE CORPORATION COMMISSION

DEC 3 1982

CONSERVATION DIVISION  
Wichita, Kansas