

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Edwards County, Sec. 8 Twp. 26 Rge. 16 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner Morris Sitrin, Inc.

Lease Name Marten #1 Well No.

Office Address Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 5/28/69 19

Plugging completed 6/3/69 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren

Producing formation Depth to top Bottom Total Depth of Well 4521 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	400	none
				5 1/2"	4521	3142'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4521', ran sand to 4450' and dumped 5 sacks of cement. Loaded hole, shot pipe at 3609', 3514', 3453', 3423', worked pipe loose and pulled 111 joints. Halliburton squeezed well with 10 sacks mud, 75 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 10th day of June 19 69

MARGARET MEECHER
NOTARY
WICHITA, KANSAS
My commission expires 2/23/71

Margaret Mecher
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15-047-00076-0000

Company- L. C. SMITHERMAN OIL
Farm- Martin No.1

SEC. 8 T. 26 R. 16W
SE SE NW

Total Depth. 4516'
Comm. 4-13-58 Comp. 4-29-58
Shot or Treated.
Contractor. L. C. Smitherman Drlg. Co.
Issued. 3-7-59

County Edwards
KANSAS



CASING:

8 5/8" 400' cem w/225 sx.
5 1/2" 4520' cem w/100 sx.

Elevation: 2085' DF

Production. 22 BOPD

Figures Indicate Bottom of Formations.

soil & clay	200
shale	287
sandy shale	400
shale & sand	940
shale	1336
shale & lime strks	1413
shale & lime	2124
lime	2325
lime & shale	3558
lime	3810
lime & shale	3986
lime	4237
lime & shale	4428
Mississippi	4429
lime & shale	4445
lime & sand	4452
lime, sand & shale	4505
lime	4516
Total Depth	

TOPS: SCOUT	
Heebner	3785
Brown Lime	3928
Lansing	3942
Cherokee Sand	4417
Mississippi	4428
Kinderhook	4446
Viola	4501

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1969
CONSERVATION DIVISION
Wichita, Kansas

Follow up
on well plugging Application
Date 5-8-1969