

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Edwards County, Sec. 8 Twp. 26S Rge. 16 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines NW NE SE

Lease Owner National Cooperative Refinery Association

Lease Name KNOWELS Well No. 1

Office Address 305 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed October 12 1959

Application for plugging filed December 6 1963

Application for plugging approved December 9 1963


Plugging commenced December 14 1963

Plugging completed December 20 1963

Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production April 30 1962

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well A. Elving

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4482 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	438'	None-Cemented
				5 1/2"	4478'	2500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 4410' and dumped 5 sacks of cement. Shot pipe at 4086', and wouldn't come. Shot pipe at 3982', could not pull. Shot pipe at 3487', at 3248', at 2986' at 2887' at 2784', still could not pull. Shot pipe off at 2500' and recovered 77 joints, 5 1/2" casing. Mudded hole to 280' and set 10' rock bridge plus 26 sacks of cement. Mudded hole to 40' and set 10' rock bridge plus 10 sacks of cement on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1964

1-3-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock
Address 411 South Buckeye, Stafford, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
C. R. Sears (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears G. R. Sears

305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 1964.

My commission expires April 29, 1965

Norma Richey
Norma Richey Notary Public.

DRILLER'S LOG

COMPANY: NATIONAL COOPERATIVE REFINERY ASSN.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: KNOWLES #1
 LOCATION: C 1/4 NW NE SE SEC. 8-26S-16W
 EDWARDS COUNTY, KANSAS
 COMMENCED: 9-18-59
 COMPLETED: 9-30-59

15-047-10026-0000

0	80	Lime
80	220	Sand and Shale
220	438	Shale and Shells
438	1060	Shale and Shells
1060	1095	Anhydrite
1095	1580	Shale and Shells
1580	2000	Shale and Shells
2000	2235	Lime
2235	2305	Lime
2305	2348	Lime
2348	2440	Lime
2440	2535	Lime
2535	2845	Lime and Shale
2845	3260	Lime and Shale
3260	3660	Lime and Shale
3660	3755	Lime and Shale
3755	3820	Lime
3820	3905	Lime and Shale
3905	3990	Lime
3990	4045	Lime
4045	4140	Lime
4140	4225	Lime
4225	4275	Lime
4275	4325	Lime
4325	4423	Lime
4423	4425	Miss. Lime
4425	4442	Lime and Chert
4442	4480	Viola
	<u>4480</u>	<u>Rotary Total Depth</u>

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1963

CONSERVATION DIVISION
Wichita, Kansas

Set 8 5/8" surface casing @ 438' with 285 sacks Sunset cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Knowles, located in the Center of the Northwest Quarter of the Northeast Quarter of the Southeast Quarter (C 1/4 NW NE SE) of Section 8, Township 26 South, Range 16 West, Edwards County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin
FRANK HAMLIN

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 5th day of October, 1959.

Juanita M. Green
Juanita M. Green, Notary Public

My Commission Expires:
April 23, 1963