


15-047-10078-00-01

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Edwards County, Sec. 9 Twp. ²⁶ 25 Rge. 16 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NE SW ~~SE~~ NW

Lease Owner Leben Drilling, Inc.

Lease Name Parker Well No. 1

Office Address P. O. Box 486 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 5-1-64 19

Application for plugging approved 5-2-64 19

Plugging commenced 5-2-64 19

Plugging completed 6-17-64 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation Depth to top Bottom Total Depth of Well PR 1502 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	432	None
				5 1/2	None	3002'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaning out cellar.

Rigging up unit. Plugging off bottom. Sanded to 4400' and 5 sacks of cement.

Shot well at 3518'. Working pipe. Shot at 2000'. Working pipe.

Working pipe. Spotting oil. Pumped 70 bbl of oil and 60 bbl of water.

Working pipe. Pulling pipe.

Pulling pipe.

Plugging well. Squeezed well with 75 sacks of cement and 15 sacks of mud.

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1964

6-23-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of June 19 64

My commission expires May 27, 1965

Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1964

DRILLER'S LOG

CONSERVATION DIVISION
Wichita, Kansas

COMPANY:	Leben Drilling, Inc.
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	PARKER #1 WASHDOWN
LOCATION:	NE SW NW Sec. 9-26-16W
	EDWARDS COUNTY, KANSAS
COMMENCED:	8-6-62
COMPLETED:	8-8-62

15-047-10078-00-01

0 4502 Washed Down
 4502 Rotary Total Depth - Set 5 1/2" Casing

8 5/8" surface casing set @ 432' by Previous Operator.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Parker #1 Washdown, located NE SW NW of Section 9, Township 26, Range 16 West of Edwards County, Kansas, as reflected by the files of Leben Drilling, Inc.


 Byron Johnson

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 9th day of August, 1962.


 Ulanda Nichols

My Commission Expires:
April 1, 1963

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:
COMMENCED:
COMPLETED:

Leben Drilling, Inc.
LEBEN DRILLING, INC.
PARKER #1 WASHDOWN
NE SW NW Sec. 9-26-16W
EDWARDS COUNTY, KANSAS
8-6-62
8-8-62

15-047-10078-00-01

0 4502
4502

Washed Down
Rotary Total Depth - Set 5 1/2" Casing

8 5/8" surface casing set @ 432" by Previous Operator.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Parker #1 Washdown, located NE SW NW of Section 9, Township 26, Range 16 West of Edwards County, Kansas, as reflected by the files of Leben Drilling, Inc.

Byron Johnson

Byron Johnson

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 9th day of August, 1962.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
April 1, 1963

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1962

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY: NATIONAL COOPERATIVE REFINERY ASSOCIATION
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: PARKER #1
 LOCATION: NE SW NW SEC. 9-26S-16W
 EDWARDS COUNTY, KANSAS
 COMMENCED: 10-2-59
 COMPLETED: 10-17-59

15-047-10078-0000

0	90	Sand
90	260	Sand and Shale
260	432	Shale and Shells
432	925	Shale and Shells
925	1067	Shale and Redbed
1067	1095	Anhydrite
1095	1460	Shale and Shells
1460	1960	Shale and Lime
1960	2175	Lime and Shale
2175	2260	Lime
2260	2410	Lime
2410	2485	Lime
2485	2655	Lime and Shale
2655	2830	Lime and Shale
2830	2974	Lime and Shale
2974	3055	Lime and Shale
3055	3375	Lime and Shale
3375	3670	Lime and Shale
3670	3722	Lime
3722	3845	Shale and Lime
3845	3950	Lime
3950	4130	Lime
4130	4310	Lime
4310	4370	Lime and Shale
4370	4385	Lime
4385	4415	Shale and Sand
4415	4428	Lime and Chert
4428	4464	Shale and Sand
4464	4485	Kinderhook Sand
4485	4493	Viola
4493	4500	Viola Lime
	<u>4500</u>	<u>Rotary Total Depth - D & A</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 26 1964
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" surface casing @ 432' with 285 sacks 6 hour cement.

I, Frank Hamlin do hereby certify that the above and foregoing is a true and correct copy of the log of the Parker #1, located NE SW NW of Section 9, Township 26 South, Range 16 West, Edwards County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin

 Frank Hamlin

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS.

Subscribed and sworn to before me, a Notary Public, in and for Sedgewick County, Kansas, this 22nd day of October, 1959.

Juanita M. Green

 Juanita M. Green, Notary Public

My Commission Expires:
 April 23, 1963