

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.047-20536-0000

API NUMBER 6/14/79

LEASE NAME SCHULTZ #4

WELL NUMBER #4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 9 TWP. 26 RGE. 16 W (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 1/5/88

Plugging Completed 1/25/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PATTON OIL COMPANY

ADDRESS 672 W. 4th Street, Hoisington, KS 67544

PHONE#(316) 653-2277 OPERATORS LICENSE NO. 5992

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? DODGE CITY DIST #1

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4459'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	475'	None
				5 1/2"	4452'	2361.95'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged bottom with sand to 4400' and 5 sacks of cement. Shot pipe

@2540', 2421', and 2361' and pulled total of 60 joints of 5 1/2" Casing.

Used Allied Cementing to plug surface with 4 hulls, 10 gel, 50 cement,

10 gel, 1 hull, 8 5/8" Plug, and 120 sacks of econolite. Plugging

(If additional description is necessary, use BACK of this form.) Complete.

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address Box 347, Chase, KS 67524

STATE OF Kansas COUNTY OF RICE, ss.

MIKE KELSO

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Bx 347, Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 26 day of January 1988

Jane Hoover
Notary Public

My Commission Expires:



1-28-1988
Form CP-4
Revised 07-86