

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -049- 20666-0000 (of this well)

Operator's Full Name Oil Properties Co. Inc.

Complete Address P.O. Box 335, Andover, Kansas 67002

Lease Name Parker B Well No. #1

Location SE SE SE Sec. 5 Twp. 26S Rge. 16W (E) (W)

County Edwards Total Depth 4484'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Sterling, Kansas License No. 683

Operation Completed: Hour 2:30 Day 31 Month 3 Year 1981
PM

The Above well was plugged as follows:

448' of 8 5/8" W/400 sxs
4 1/2" - 4478' W/125 sxs Top of Cement 3950'
Perfs 4411' - 4418' 4438' - 4445' 4477' - 4479'
Sand to 4350' & W/4 sxs cement-15 sxs gel-6 sxs hulls-10 sxs gel
Plug W/125 sxs 50/50 poz-4% gel & 3% cc
Recovered 3910' of 4 1/2" csg. S.I.P. 300#

RECEIVED
STATE CORPORATION COMMISSION
APR - 3 1981
4-3-81
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: McLester
Well Plugging Supervisor

INVOICED
DATE 4-6-81
INV. NO. 5039-W