

R.

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 047 - 20512-6000 (of this well)

Operator's Full Name F. G. Holl.

Complete Address 6427 E. Kellogg, Wichita, Ks. 67207

Lease Name Shannon Well No. 1-7

Location C NW SW Sec. 7 Twp. 26 Rge. 16 (E) W

County Edwards Total Depth 4655

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling.

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 3:30 Pm. Day 6 Month 9 Year 1979

The above well was plugged as follows:

434' 8 5/8" casing w/350 sax cement. 4 1/2" casing set at 4631' w/150  
sax cement. Open hole-Sand back to 4600'-Top sand w/4 sax mixed cement  
w/ dump bailer-Pull 3400' 4 1/2" casing-Sun mixed & pumped 8 sax hulls-  
25 sax gel-125 sax 50/50 posmix cement w/4% gel & 3% cc to top of csng.  
Shut in w/150# pressure.

SEP 11 1979

I hereby certify that the above well was plugged as herein stated.  
Wichita, Kansas

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 9-12-79

INV. NO. 0411-W