

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 4 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Wichita Iron & Metal Corp., Inc. 15-047-00073-0000

Complete Address: Box 2421, Wichita, Kansas

Lease Name Welsch Well No. # 1

Location SW/4 Sec. 9 Twp. 26 Rge. 16 (E) (W) W

County Edwards Total Depth 4496'

Abandoned Oil Well X Gas Well    Input Well    SWD Well    D & A   

Other well as hereafter indicated:   

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:15AM Day 31st Month March Year 1966

The Above well was plugged as follows:

239' of 8 5/8" surface pipe, cement circulated. 4496' of 5 1/2", no record on  
cement. Top perferation 4393'. Bottom of the hole was sanded to 4375', and  
cemented with 5 sacks, through the dump bailer. 2930' of 5 1/2" long string was  
recovered from the hole. Bridge plug was pushed in fluid to 239', rock bridge  
from 239' to 230', 5 sacks of cement was mixed in a barrel, and put on plug at  
230', through the dump bailer, and let set over-night. Next day hole was bailed  
dry, and 20 sacks of cement was added to the plug. Hole was filled with mud to  
40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/4/66

INV. NO. 2982-W