

4 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leben Drilling Inc. 15-047-10078-00-01

Complete Address: 912 Central Bldg., Wichita, Kansas

Lease Name Parker Well No. # 1

Location NE SW ^{NW} SW Sec. 9 Twp. 26 Rge. 16 (E) W (W) W

County Edwards Total Depth 4502

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 4:00PM Day 17th Month June Year 1964

The Above well was plugged as follows:

432' of 8 5/8" surface pipe, cemented with 285 sacks. 4501' of 5 1/2" long
string, cemented with 125 sacks. Top perferation 4410'. Bottom of hole
was sanded to 4400', and cemented with 5 sacks. Hole was squeezed. 15
sacks of Gel-Mud and 75 sacks of cement was pumped into surface pipe,
through an 8 5/8" swage, to a pressure of 250 lbs. A wiping plug was
run between the mud and the cement. This cementing was done by Forbes
Casing Pulling Inc.

3000' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/19/64

INV. NO. 9891-W