

KANSAS

FORM CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

MAR 31 1981

3-31-81

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 047-20625-0000 (of this well)

Operator's Full Name Alpine Drilling Co., Inc.

Complete Address 200 East First, Suite 500, Wichita, Kansas 67202

Lease Name Ellis Well No. #1

Location C/ SW SW Sec. 17 Twp. 26S Rge. 16W (E) (W)

County Edwards Total Depth 4653'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling Buck Unruh-Operator

Address Box 176 Chase, Kansas 67524 License No. _____

Operation Completed: Hour 3:30 Day 24 Month 3 Year 1981
PM

The Above well was plugged as follows:

265' of 8 5/8" circ. 5 1/2" 4652' W/125 sxs

Plug Back to 4550' Perfs 4502' to 4512'

Sand Back to 4475' & 5 sxs cement

Squeezed 8 5/8" csg. W/15 gel-6 hulls-10 gel

Released Plug & Displaced W/125 sxs 50/50 poz-4% gel-3% cc

Recovered 3480' of 5 1/2" casing SIP 300#

Cemented by Allied

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4-6-81

INVOICE NO. 5040-W