

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1964

3-24-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Inger Oil Company 15-047-00135-0000

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name Schultz "X" B Well No. # 3

Location C NE SE Sec. 21 Twp. 26 Rge. 16 (E) (W)W

County Edwards Total Depth 4560

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 1:30PM Day 20th Month April Year 1964

The Above well was plugged as follows:

390' of 8 5/8" surface pipe, cement circulated. 4560' of 5 1/2" long string, cement-
ed with 150 sacks. Top perferation 4450'. Bottom of hole was sanded to 4440', and
cemented with 5 sacks. Fluid in hole was bailed down to 200', plug was set at 200
with 10' of rock bridge, and cemented with 25 sacks. Hole was filled with mud to
40', with 10' of rock, and cemented with 10 sacks to base cellar. 2887' of 5 1/2"
long string was recovered from the hole.

Knight Casing Pulling Co. failed to contact me for plugging orders on this hole,
and they went ahead and plugged this well on their own accord, with out my plugg-
ing orders or supervision. If any plugging trouble developes in the future I feel
that Knight Casing Pulling Co. should be fully responsible. I had to call them on
the phone, and they told me this is how they plugged this hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/27/64

INV. NO. 9021-4