

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sitrin Pet. Corp. 15047-10109-0000

Complete Address Box 693 Great Bend, Ks 67530

Lease Name Schultz -A Well No. 2

Location C/NW/SE Sec. 21 Twp. 26 Rge. 16 (E) (W) W

County Edwards Total Depth 4495

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks 67524 License No. 436

Operation Completed: Hour 3:00PM Day 20 Month 3 Year 1970

The above well was plugged as follows:

325 ft of 8 5/8 surface pipe circulated with cement. 4480 ft of 5 1/2
long string cemented with 150 sacks. Top perf 4492 ft. Sand to
4465 ft, 5 sacks cement with bailer. Pulled 3400 ft of 5 1/2. Mud to
250 ft, 10 ft rock bridge, 25 sacks cement. Mud to 40 ft, 10 ft
rock bridge, 10 sacks cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Russell Bilesstein
Well Plugging Supervisor

INVOICED

DATE 3/23/70

INV. NO. 1619-11