

15-155-20827-0000

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Diamond Shamrock Corporation

API NO. 15-155-20,827

ADDRESS P. O. Box 631
Amarillo, Texas 79173

COUNTY Reno

**CONTACT PERSON Kent Kirkpatrick
PHONE 806-378-3844

FIELD Laredo East

PROD. FORMATION Dry

PURCHASER _____

LEASE Verba Brooks

ADDRESS _____


WELL NO. #2

DRILLING CONTRACTOR H-30 Drilling Co.
ADDRESS 251 N. Water Suite 10
Wichita, Ks 67202

WELL LOCATION C, SW, NW

1980 Ft. from North Line and
990 Ft. from West Line of
the SEC. 20 TWP. 26S RGE. 8W

PLUGGING CONTRACTOR H & H Casing Pullers
ADDRESS Box 563
Burton, Ks 67202



WELL PLAT
KCC
KGS
MISC _____
(Office Use)

TOTAL DEPTH 3969' PBTD _____

SPUD DATE 10-10-81 DATE COMPLETED P&A 3-20-82

ELEV: GR 1639' DF _____ KB 1647'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	410'	Common	300 sx	3% cc
*Production	7 7/8"	5 1/2"	15.5#	3964'	Thix-o-tropic	300 sx	---
*Recovered 1870' of 5 1/2" casing when well was plugged.							

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3 SPF	5" csg. gun	3379-3383
TUBING RECORD			2 SPF	1 1/2" csg. gun	3658-3670
			2 SPF	1 1/2" csg. gun	3561-3570
Size	Setting depth	Packer set at	2 SPF	1 1/2" csg. gun	3514-3518
2 3/8"	Pulled		2 SPF	1 1/2" csg. gun	3377-3381

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
acid w/250 gals 15% FCA, sq. w/100 sx class "H"	3379-3383
acid w/500 gals 15% MCA. Set CIBP @ 3640'	3658-3670
acid w/500 gals 15% MSA	3561-3570
acid w/1500 gals 15% MSA. Set CIBP @ 3550'	3514-3518
acid w/2000 gals 7 1/2% MCA. Set CIBP @ 3500'	3377-3381
Set 5 1/2" rubber plug @3300' w/5sx cmt. pmpd 100 sx 50/50 Poz. @ 3'-355'	

Date of first production P & A on 3-20-82 Producing method (flowing, pumping, gas lift, etc.) Gravity

RATE OF PRODUCTION PER 24 HOURS: Oil _____ bbls, Gas _____ MCF, Water _____ %

Disposition of gas (vented, used on lease or sold) _____ Perforations **RECEIVED**

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

*Well completed as dry hole and plugged on 3-20-82.

Please see attached Plugging Record

CON. **Rec'd 3-1-81**

Name of lowest fresh water producing stratum _____ Depth 200'

Estimated height of cement behind Surface Pipe Surface

DV USED? No

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
Topeka	2586			
Heels	3092			
Toronto	3108			
Br. Lar	3282			
Lans.	3333			
Stark Sh.	3616			
Soope	3659			
Miss	3916			

AFFIDAVIT

STATE OF Texas, COUNTY OF Potter SS,

Kent Kirkpatrick OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,
 DEPOSES THAT HE IS Production Specialist (FOR)(OF) Diamond Shamrock Corporation
 OPERATOR OF THE Verba Brooks LEASE, AND IS DULY AUTHORIZED TO MAKE
 THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. #2 ON
 SAID LEASE HAS BEEN COMPLETED AS OF THE 29 DAY OF March, 19 82, AND THAT
 ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.
 FURTHER AFFLIANT SAITH NOT.

(S) Kent Kirkpatrick

SUBSCRIBED AND SWORN BEFORE ME THIS 29th DAY OF March 19 82

Patti Jones
NOTARY PUBLIC

MY COMMISSION EXPIRES: 5-06-82 Patti Jones