


WELL PLUGGING RECORD 15-155-00002-0000

Give All Information Completely,
Make Required Affidavit,
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

_____ Reno _____ County, Sec. 12 Twp. 26 Rge. 9 (E) _____ (W) x
Location as "NE/CNW/SW" or footage from lines _____ NW NW NE
Lease Owner _____ Messman-Rinehart Oil Co.
Lease Name _____ Pafford _____ Well No. #1
Office Address _____ 1432 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19 _____
Application for plugging filed _____ 19 _____
Application for plugging approved _____ 19 _____
Plugging commenced _____ 12-7-68 _____ 19 _____
Plugging completed _____ 12-12-68 _____ 19 _____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well _____ Gilbert Tomer
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3981' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3980'	3230-17'
				8 5/8"	232'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3790'. Mixed and ran 5 sacks cement thru dump bailer.
Mudded hole to 130', set 10' rock bridge. Mixed and ran 25 sacks cement thru dump bailer. Mudded hole to 40', set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1968
CONSERVATION DIVISION
Wichita, Kansas

12-16-68


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____ Southwest Casing Pulling Co.
Address _____ Box 364, Great Bend, Kansas

STATE OF _____ Kansas _____, COUNTY OF _____ Barton _____, ss.
_____ Southwest Casing Pulling Co. _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____ W. C. Spencer _____
_____ Box 364, Great Bend, Kansas _____
(Address)

Subscribed and sworn to before me this _____ 13 _____ day of _____ December _____, 1968



_____ Sidney Miller _____
Notary Public.

Well Record

Location:	NW NW NE, Sec. 12-26S-9W Reno County, Kansas	Commenced:	November 21, 1957
Operator:	Messman-Rinehart Oil Company 518 Petroleum Building, Wichita, Kansas	Completed:	December 4, 1957 (Rotary)
Contractor:	Messman-Rinehart Oil Company 518 Petroleum Building Wichita, Kansas	Elevation:	1674' R/B
Casing Record:	8-5/8" @ 232' w/150 sx. cement 5-1/2" @ 3980' w/75 sx. cement	Production:	Gas

*** LOG ***

Shale	45
Shale & Red Bed	205
Shale & Shells - Salt	1055
Shale & Shells	1295
Anhydrite	1330
Lime & Shale	1445
Lime & Shale	1610
Lime	1755
Lime & Shale	1885
Lime & Shale	2030
Shale & Lime Streaks	2180
Shale	2415
Lime - Shells & Shale	2550
Shale w/Lime Streaks	2680
Lime & Shale	2890
Lime - Shale	3042
Lime & Shale	3132
Lime & Shale	3230
Shale & Lime	3367
Lime	3420
Lime	3465
Lime	3527
Lime	3565
Lime	3595
Lime	3605
Lime & Shale	3655
Lime & Shale	3705
Lime & Shale	3743
Lime & Shale	3810
Lime & Shale	3880
Lime & Shale	3890
Chert "Miss."	3903
Chert	3938
Chert & Lime	3951
Shale - Lime	3997
Shale	4075
Lime & Shale	4146
Shale & Lime	4160 R.T.D.

*No comp. data
attached*

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1969
CONSERVATION DIVISION
Wichita, Kansas

Electric Log Tops:

1-22-69

Brown Lime	3316 (-1642)
Lansing	3334 (-1660)
Mississippian	3891 (-2217)
Kinderhook	3957 (-2283)
Viola	(Log didn't read)
	4156 (-2482) (sample)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

MESSMAN-RINEHART OIL COMPANY

By: *J. A. Gilliland*
J. A. Gilliland

Subscribed and sworn to before me
this 22th day of December, 1957.

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1960