

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-155-20,895-0000

LEASE NAME E. Johnson #1

WELL NUMBER

SPOT LOCATION 330' FNL, 660' FNL

SEC. 11 TWP. 24 RGE. 4w (E) or (W) NW/4

COUNTY Reno

Date Well Completed

Plugging Commenced 11/28/84

Plugging Completed 12/3/84

*Alex Ward*

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Excalibur Production Co., Inc.

ADDRESS P.O. Box 278, McPherson, Ks. 67460

PHONE # (316) 241-1265 OPERATORS LICENSE NO. 5330

Character of Well  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filled? If not, is well log attached?

Producing formation Depth to top bottom T.D. 3358'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				12 3/4	290'	none
				5 1/2"	3353'	2191'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3300' & 5 sacks cement. Shot pipe at 2821', 2627', 2415', & 2191'. Pulled 58 joints of pipe. Mixed 6 sacks hulls with 20 sacks gel, released plug & ran 200 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) Box 347, Chase, Ks. 67524


DEC 07 1984  
12-7-84  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1984

IRENE HOOVER  
State of Kansas  
My Comm. Exp. Aug. 15, 1985

*Irene Hoover*  
Notary Public

My Commission expires:



# Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

October 11, 1982

COMPANY: EXCALIBUR PRODUCTION CO., INC.  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: E. JOHNSON #1  
 LOCATION: 330' FNL & 660' FNL NW/4 Section 11-24-4W,  
 Reno County, Kansas  
 COMMENCED: October 6, 1982  
 COMPLETED: October 10, 1982  
 ELEVATION:

0	to	180	Sand
180	to	230	Clay
230	to	295	Shale
295	to	825	Shale & Lime
825	to	1455	Lime & Shale
1455	to	1970	Shale & Lime
1970	to	2270	Lime & Shale
2270	to	2660	Shale & Lime
2660	to	3100	Lime
3100	to	3270	Lime & Shale
3270	to	3340	Shale & Lime
3340	to	3358	Lime
		3358	T. D.

Cut 17' hole to 288' and run 290' of 12 3/4" surface pipe, cemented with 125 sacks of cement at 289' Plug down at 2:00 P. M., October 6, 1982. Run 3364' of 5 1/2" casing, cemented with 90 sacks of cement at 3353', 5 feet off bottom. Plug down at 4:15 P. M., October 10, 1982.

TOPS: MISSISSIPPI - 3306'

Measurements taken from E. B.

### CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your E. Johnson #1, located on the 330' FNL & 660' FNL NW/4 Section NW/4 Section 11-24-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

*P. E. Plouffe*  
 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 11th day of October, 1982.

*Johnnie L. Schmidt*  
 Johnnie L. Schmidt - Notary Public

JOHNNIE L. SCHMIDT  
 McPherson County, Kansas  
 My Appt. Exp. June 23, 1985

*Reed*  
 11-24-84