


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Edwards County, Sec. 17 Twp 26S Rge. 16W (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines C SE NW

Lease Owner Stateswide Oil Corporation

Lease Name Welsch Well No. 1 Calif.

Office Address 8530 Wilshire Blvd., Suite 512, Beverly Hills,

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-8-62 19

Application for plugging filed 9-8-62 19

Application for plugging approved 9-8-62 19

Plugging commenced 9-8-62 19

Plugging completed 9-8-62 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Stafford, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4688 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	209'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set:

1st plug Set @ 280' with 20 sacks of cement.

2nd plug set @ 35' with 10 sacks of cement.  
(2 sacks in the rat hole)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 12 1962

CONSERVATION DIVISION  
Wichita, Kansas

9-12-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Byron Johnson

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of September, 1962

My commission expires April 1, 1963

Ulanda Nichols

Notary Public.

DRILLER' LOG

15-047-00254-0000

COMPANY: Stateswide Oil Corporation  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: WELSCH #1  
 LOCATION: C SE NW Sec. 17-26S-16W  
 EDWARDS COUNTY, KANSAS  
 COMMENCED: 8-28-62  
 COMPLETED: 9-8-62

0	376	Sand & Shale
376	470	Redbed
470	700	Sand
700	1160	Shale & Redbed & Sand
1160	1885	Shale
1885	2200	Shale & Lime
2200	2385	Lime with Shale
2385	2510	Lime
2510	2660	Lime with Shale Streaks
2660	2715	Lime & Shale
3715	3820	Lime
3820	3860	Lime & Shale
3860	4488	Lime
4488	4583	Lime & Chert
4583	4688	Lime
	<u>4688</u>	<u>Rotary Total Depth - D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP. 12 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" used surface casing @ 309' Cemented with 250 sacks of Sunset Cement by Sun Oilwell Cementing.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Welsch #1, located C SE NW of Section 17, Township 26 South, Range 16 West, Edwards County, Kansas as reflected by the files of Leben Drilling, Inc.

Byron Johnson  
 Byron Johnson

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 10th day of September, 1962.

Ulanda Nichols  
 Ulanda Nichols, Notary Public

My Commission Expires:  
 April 1, 1963