

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-047-20625-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 17 TWP 26^S RGE: 16W E/W
 Location as in quarters or footage from lines:
C of SW SW

Lease Owner Alpine Drilling Co., Inc.
 Lease Name Ellis #1 Well No. _____
 Office Address Box 28, Ellinwood, Ks.
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 3/20/81
 Plugging completed 3/24/81
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
 Producing formation _____ Depth to top _____ bottom T.D. 4653'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	265	None
				5-1/2"	4652	3496

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Moved in. Made bottom hole plug back with sand to 4475. Mixed and ran 5 sacks cement.
thru dump baler. Made shots at 3600 and 3480. Pulled total of 88 joints. Squeezed hole
with 15 sacks gel, 6 sacks hulls and 10 sacks gel. Released plug and displaced with
125 sacks 50/50 pos 4% gel 3% cc. Plugging complete.

RECEIVED
 STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor KELSO CASING PULLING APR - 6 1981
CHASE, KANSAS 11-6-81


CONSERVATION DIVISION
 Wichita, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 81

My Commission expires:



Joan Kelso
 Notary Public.