

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

15-047-2185-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Edwards SEC. 17 TWP. 26S RGE. 16 E/W  
Location as in quarters or footage from lines:  
C SE SW


Lease Owner B.A.N. Oil Co.

Lease Name Ellis Well No. 1

Office Address Box 418, Booneville, Missouri 65233

Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole

Date Well Completed June 10, 1984

Application for plugging filed June 8, 1984

Plugging commenced June 8, 1984

Plugging completed June 10, 1984

Reason for abandonment of well or producing formation Dry hole

Locate Well  
correctly on above  
Section Plat.

Was permission obtained from the Conservation Division or it's

Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dodge City office

Producing formation   Depth to top   bottom   T.D. 4650KB

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from   feet to   feet for each plug set. Plugged as follows:


Filled hole with mud; pumped 50 sx 60/40 Pozmix, 2% gel, 3% cc, through open end drill pipe @ 1105', mud to 560', pumped 60sx through open end drill pipe, mud to 40', 1/2 sx hulls, 8 plug for solid bridge, pumped 10 sx to base of cellar, 15 sx in rathole, 10 sx in mousehole, 10 sx in water well. Completed @ 9:30 AM 6-10-84 by Halliburton.

RECEIVED  
STATE CORPORATION COMMISSION

6-15-84 JUN 15 1984

— (If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Cougar Drilling Co., Inc. CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
John S. Crowe (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.



(Signature) Cynthia L. Jackson  
555 N. Woodlawn, #114, Wichita  
(Address) 67208

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 84

Cynthia L. Jackson  
Notary Public.

My Commission expires: 25-86

15-047-2183-000

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR B.A.N. Oil Co.

LEASE Ellis #1

SEC. 17 TWP. 26SRGE. 16W

## FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-down tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand, gravel, clay	0	200		
Blue shale	200	440		
Redbeds	440	515		
Redbeds, shale, sand	515	1105		
Anhydrite	1105	1127		
Shale	1127	2175		
Shale, lime	2175	3600		
Lime, shale	3600	3995		
Shale, lime	3995	4115		
Kansas City	4115	4200		
Lime, shale	4200	4405		
Lime	4405	4565		
Viola	4565	4650		

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 15 1984  
CONSERVATION DIVISION  
Wichita, Kansas