

15-647-10080-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County. Sec. 21 Twp. 26S Rge. 16 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner National Cooperative Refinery Association

Lease Name Schultz Well No. 2

Office Address 305 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 22, 19 58

Application for plugging filed December 23, 19 58

Application for plugging approved December 24, 19 58

Plugging commenced December 22, 19 58

Plugging completed December 22, 19 58

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lewis Brock

Producing formation Depth to top Bottom Total Depth of Well 4690 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	432'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 400', set plug with 20 sacks of cement plus 1/2 sack of hulls. Mudded hole to 40', set plug with 20 sacks of cement and 1/2 sack of hulls. Filled on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1959
CONSERVATION DIVISION
WICHITA, KANSAS

1-21-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling Company

Address 905 Central Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
C. R. Sears (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears C. R. Sears

305 Rule Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 20th day of January, 19 59

My commission expires November 26, 1960.

Notary Public. Nell McComb

PLUGGING
FILE SEC. 21 T. 26 R. 16W
BOOK PAGE 6 LINE 9

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:
COMMENCED:
COMPLETED:

NATIONAL COOPERATIVE REFINERY ASSOCIATION
LEBEN DRILLING, INC.
SCHULTZ #2
SE $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$ SEC. 21-26S-16W
EDWARDS COUNTY, KANSAS
12-7-58
12-22-58

15-047-10080-0000

0	100	Surface sand & Shale	
100	275	Sand	
275	410	Shale	<u>LOG TOPS:</u>
410	1020	Redbed	Heebner 3838
1020	1070	Shale & Redbed	Toronto 3855
1070	1105	Anhydrite	Douglas 3874
1105	1410	Shale & Shells	Br. Lime 3992
1410	1770	Shale	Lansing 4008
1770	2075	Shale & Shells	Bs. K.C. 4350
2075	2450	Lime	Cherokee 4478
2450	2810	Shale & Lime	Cong. 4492
2810	2890	Shale & Shells	Mississippi 4517
2890	3075	Shale	Kinderhook 4538
3075	3215	Shale & Shells	Kinderhook Sand 4600
3215	3295	Shale	Viola 4662
3295	3620	Shale & Lime	
3620	3635	Lime	Elevation 2111 K.B.
3635	3720	Shale & Lime	
3720	3875	Lime	
3875	3945	Shale & Lime	
3945	4330	Lime	
4330	4515	Shale, Lime & Chert	
4515	4660	Shale & Sand	
4660	4690	Chert	
	4690	<u>Rotary Total Depth - D & A</u>	

Set 426' of 8 5/8" surface casing with 285 sacks cement & 6 sacks CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schultz #1, located SE $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$ of Section 21, Township 26 South, Range 16 West, Edwards County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss:

JAN 21 1959
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 30th day of December, 1958.

Ruth N. Benjamin
Ruth N. Benjamin, Notary Public

My Commission Expires:
June 17, 1961

PLUGGING
FILE SEC. 21 T. 26 R. 16W
BOOK PAGE 6 LINE 9