


15-047-10188-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Edwards County, Sec. 21 Twp. 26 Rge. 16W (E) (W)
Location as "NE/CNW&SW" or footage from lines. C SW NE
Lease Owner Sitrin Petroleum Company
Lease Name Schultz D#1 Well No.
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3/13/72 19
Plugging completed 3/17/72 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4546 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	295	none
				5 1/2"	4540	2682'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 4530' and dumped 5 sacks of cement. Loaded hole, shot pipe at 3021', 2710', pulled 82 joints. Allied pumped 2 sacks hulls, 20 sacks gel and 100 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1972
CONSERVATION DIVISION
Wichita, Kansas

4-17-72

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March, 1972

Margaret Melcher
Notary Public.

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company L. C. SMITHERMAN—OIL PRODUCER
Farm: Schults "D" No. 1

SEC. 21 T. 26 R. 16W
C SW NE

Total Depth. 4540'
Comm: 6/9/59 Comp. 6/26/59
Shot or Treated.
Contractor. L. C. Smitherman Drilling Co.
Issued. 5/21/60

County Edwards
KANSAS



CASING:

8 5/8" 295' w/225 sks.
5 1/2" 4546' w/100 sks.

Elevation. 2079 RB

Production. 140 BOPD

Figures indicate Bottom of Formations.

15-047-1618-0000

surface clay & sand	298
red bed	675
red bed & sand	970
red bed	1075
lime	1175
shale & shells	1400
shale	1860
shale & lime	2150
lime	2830
lime & shale	3000
lime	3125
shale & sandy lime	3150
lime & shale	3235
lime	3290
lime & shale	3355
lime & shale streaks	3430
lime & shale	3495
shale	3580
lime & shale	3655
shale	3772
lime & shale	4020
lime	4396
lime & shale	4500
lime	4531
shale	4540

Total Depth

TOPS: SCOUT

Heebner	3797
Toronto	3822
Douglas	3833
Brown lime	3946
Lansing	3955
Base Kansas City	4300
Fort Scott	4318
Cherokee shale	4425
Conglomerate	4438
Mississippi	4466
Kinderhook shale	4514
Kinderhook sand	4534

RECEIVED
STATE CORPORATIONS COMMISSION
MAR 2 1972
CONSERVATION DIVISION
Wichita, Kansas