

15-047-20864-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY EDWARDS SEC. 21 TWP. 26S RGE. 16 E/W
 Location as in quarters or footage from lines:
C NE SE NW 700' FNL 2600' FWL

Locate Well
 correctly on above
 Section Platt.

Lease Owner BENSON MINERAL GROUP, INC.
 Lease Name SCHULTZ L Well No. 1-21
 Office Address 1726 CHAMPA ST. SUITE 600 DENVER, CO. 80202
 Character of Well (Completed as Oil, Gas or Dry Hole): OIL
 Date Well Completed 7-20-81
 Application for plugging filed 8-16-82
 Plugging commenced 9-16-82
 Plugging completed 9-21-82
 Reason for abandonment of well or producing formation DRY

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well STEVE DURRANT
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4638'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				4 1/2"		1,830.15'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

SET BOTTOM PLUG 4470' 15' ROCK BRIDGE - 4 SX CEMENT
ALLIED CAME OUT 9-27-82 AND FILLED WITH 3 HULLS - 10 JEL - 50SX CEMENT
1 HULL - 15 JEL - WOODEN PLUG - 100SX CEMENT 50/50 POZ. WITH 2% JEL 3% C.C.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H & H CASING PULLING CO.
2900 ACRES RD. # 107 HUTCHINSON, KS. 67501

STATE OF KANSAS COUNTY OF RENO, ss.
DONALD H. HURST (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Donald H. Hurst
2900 Acres Rd. # 107
Hutchinson, Kansas

SUBSCRIBED AND SWORN to before me this _____ day of _____, 1982



22nd day of February, 19 82
Madeline Hurst
 Notary Public.

My Commission expires: _____

OCT 04 1982
 CONSERVATION DIVISION
 Wichita, Kansas

10-4-82

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

S. 21 T. 26S R. 16 ~~W~~ ~~W~~

Loc. C NESENW
County Edwards

API No. 15 — 047 — 20,864-0000
County Number

Operator: Benson Mineral Group, Inc.

Address: 1726 Champa St., Suite 600, Denver, CO 80202

Well No. 1-21 Lease Name Schultz L


Footage Location: 700 feet from (N) ~~XX~~ line 2600 feet from (E) (W) line

Principal Contractor DaMac Drilling Geologist

Spud Date 5-10-81 Date Completed 7-20-81 Total Depth 4638 P.B.T.D. 4560

Directional Deviation Oil and/or Gas Purchaser

640 Acres
N



Locate well correctly

Elev.: Gr. 2085
DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2	8 5/8		479	60-40 POZ	400	3% CaCl
Production	7 7/8	4 1/2	10.5	4633	60-40 POZ	260	18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		4520-30
			2		4538-46

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
20,000# 20-40 sn x 6000# 10-20 sn	4520-30 x 4538-46

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1982

INITIAL PRODUCTION

CONSERVATION DIVISION
Wichita, Kansas

Date of first production: 8-81	Producing method (flowing, pumping, gas lift, etc.): pumping
RATE OF PRODUCTION PER 24 HOURS	Oil: 2 bbls. Gas: 0 MCF Water: 50 bbls. Gas-oil ratio: CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

15-047-20864-0000
 Phone Plainville 913-434-2812
 Phone Kiowa 316-825-4618

ALLIED CEMENTING CO., INC.

No 30722

Home Office P. O. Box 31

Russell, Kansas 67665

Date	7-27-87	Sec.	21	Twp.	26	Range	16W	Called Out	5:00 AM	On Location	9:00 AM	Job Start	9:10	Finish	2:15
Lease	S. 21 Well No. 21			Location				Trossard 2 1/2 S. E. line			County	Edwards	State	Kans	

Contractor	?
Type Job	17. 1H. 6. Plus
Hole Size	7 1/2 T.D. 4500
Csg. Size	Depth
Tbg. Size	Depth
Drill Pipe	Depth
Tool	Depth
Cement Left in Csg.	Shoe Joint
Press Max.	Minimum 0
Meas Line	Displace
Perf.	

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Charge To	BMAC
Street	
City	State
The above was done to satisfaction and supervision of owner agent or contractor.	
Purchase Order No.	
X	Monahan, J. Kerst
CEMENT	

EQUIPMENT		
Pumptrk	No. 63	Cementer F.R.S. T.M.W. Helper J.M.W.
Pumptrk	No.	Cementer Helper
Bulktrk	158	Driver B.L.S. P.L.C.
Bulktrk	76	Driver J. P. W.H.

Amount Ordered	150 5/8 2 1/2 gal (3 1/2 cu)
Consisting of	25 gal 4 1/2 lbs
Common	
Poz. Mix	
Gel.	
Chloride	
Quickset	
Sales Tax	
Handling	
Mileage	SEP 29 1982
Sub Total	
Total	
Floating Equipment	

DEPTH of Job		
Reference:	F. J. Trossard	
	26.13	
		Sub Total
		Tax
		Total

Remarks: Mixed 3 shells 10 gal 50-100% cement

amount 15 gal 1 shell 50% cement
 O.M. V.A.C.
 THANK YOU