

15-047-10034-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County, Sec. 22 Twp. 26 Rge. 16W (87) (W)

Location as "NE/CNW%SW%" or footage from lines NW SW
Lease Owner Humble Oil Company
Lease Name Parker Well No. 1
Office Address Box 786 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 19____
Plugging completed October 28, 19 60
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4594' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

FORMATION	CONTENT	FROM	TO	REMARKS
				RECEIVED MAR 29 1966 3-29-66 CONSERVATION DIVISION Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8 5/8" - 1102' - 2 1/2" tubing 4584- Top Perf 4463'
Pumped 10 sacks cement thru tubing to bottom pulled
3000 tubing-pumped mud thru tubing and spotted 30
sacks cement-mud to 40' capped to base of cellar with
15 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Company
Address Box 579 Great Bend, Kansas

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

[Signature]
1000 Clearview Center N.W. 15th St.
Oklahoma City, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of March, 1966

North T. Nelson
Notary Public.

My commission expires 3-1-69

15-047-10034-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. HUMBLE OIL & REFINING CO.
Farm. Weldon Parker No. 1

SEC. 22 T. 26 R. 16W
C NW SW

Total Depth. 4596'
Comm. 9-20-60 Comp. 10-7-60
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 3-10-62

County Edwards
KANSAS



Elevation. 2101' RB

Production. Dry

CASING:

13 3/8" 167' cem w/300 sx.
8 5/8" 1102.60' cem w/550 sx.
2 7/8" 4583.59' cem w/225 sx.

Figures indicate Bottom of Formations.

surface soil & sand	40
sand & gravel	160
shale & sand	167
sand & gravel	275
shale & red bed	815
red bed & Anhydrite	1103
Anhydrite	1160
shale	1472
shale & shells	1945
lime & shale	2065
lime	2360
lime & shale	3075
shale & lime	3525
sandy shale & lime	3644
shale & lime	3725
lime & shale	3855
shale & lime	4076
lime	4338
lime & shale	4467
shale & sand	4477
chert	4519
sandy cherty shale	4550
sandy shale	4596
Total Depth	

TOPS: SCOUT	
Heebner	3820
Brown Lime	3969
Lansing	3984
Base Kansas City	4318
Cherokee	4428
Mississippi	4470
Kinderhook	4536
Viola	4584

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1964
CONSERVATION DIVISION
Wichita, Kansas