

15-047-20098-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Edwards County, Sec. 23 Twp. 26 Rge. 16 (E) (W)X

Location as "NE/CNW/SW" or footage from lines C/SE/SE
Lease Owner Midwestern Supply Co., Inc.
Lease Name J. H. Lewis Well No. 1
Office Address Box 825 Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ May 17, 19 72
Plugging completed _____ May 25, 19 72
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4555 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	458	None
				4 1/2	4650	3139.52'

Describe in detail the manner in which the well was plugged; indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 4500' and 4 sacks cement. Shot casing at 3953' and 3720'.
Spotted 80 bbls. oil. Shot at 3513' and 3120'. Laid down a total of 96 jts. of
4 1/2" casing. Allied squeezed well with 2 sacks hulls, 15 sacks gel and 100 sacks
cement.


RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1972 5-31-72

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.
Address P. O. Box 698 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold James W. Rockhold
Box 698 Great Bend, Kansas 67530 (Address)

Subscribed and Sworn to before me this 30th day of May, 19 72

My commission expires September 30, 1975

Cathy Miller
Cathy Miller Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

RECEIVED
 STATE CORPORATION COMMISSION

MAY 23 1972
 CONSERVATION DIVISION
 Wichita, Kansas

LEWIS #1
 C SE SE SEC. 23-28S-16W
 Edwards County, Kansas

Commenced: July 19, 1971
 Completed: August 1, 1971

OPERATOR: J. MARK RICHARDSON

15-047-20098-0000

DEPTH		FORMATION	REMARKS
From	To		
0	290	Sand	Ran 10 joints of used 28# @ 5/8" casing set @ 458' w/200 sbs common 3# CC -4# Gal, 150 Sbs Common 3# CC 2# Gal P.D. @ 2:30 PM 7/20/71 Cement Cir. Job by Globe
290	462	Shale, Shells, Redbed	
462	745	Shale, Redbed	
745	864	Shale	
864	1005	Redbed and Shale	
1005	1079	Anhydrite	
1079	2063	Shale	
2063	2185	Lime and Shale	
2185	2355	Shale and Lime	
2355	2639	Lime and Shale	
2639	2680	Lime	Ran 140 joints of @ 1/28" & 1/2" casing - set @ 4554' 1' off bottom w/150 sbs common salt sat cement. P.D. @ 5:30 PM 8/1/71 Job by Globe Centralizers on 1st, 2nd, 3rd collars.
2680	4008	Lime and Shale	
4008	4480	Lime	
4480	4485	Lime and Shale	
4485	4510	Lime	
4510	4515	Lime and Sand	
4515	4553	Lime, Shale, Sand	
4553	TD		

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE SE, Sec. 23-28S-16W, Edwards County, Kansas to the best of my knowledge and belief.

James S. Sutton II
 James S. Sutton II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 6th day of August, 1971, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

In Witness Whereof, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
 Marjorie Hall

My commission expires
 Nov. 29, 1971