

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-047-21,073-000

LEASE NAME Stegman

WELL NUMBER #3

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC 23 TWP. 26 RGE. 16 (E) or (W)

COUNTY Edwards

Date Well Completed \_\_\_\_\_

Plugging Commenced 5-10-89

Plugging Completed 10-23-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS Box 8647, Wichita, Ks. 67208

PHONE # 316-672-3440 OPERATORS LICENSE NO. 8061

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 10, 1989 (date)

by Richard Lacey and Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
 STATE CORPORATION COMMISSION

10-25-89 OCT 25 1989

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	640	None
				4-1/2"	4528'	3,085.75'

CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet, each set. Dumped sand to 4350' and 4 sacks cement. Shot casing at 3400' and 3050', Pulled 75 joints of 4-1/2" casing. Allied plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 gel, 100# hulls and 125 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 300 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold

Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 24th day of October, 1989

STATE NOTARY PUBLIC  
 IONA M. LEATHERMAN  
 Barton County, Kansas  
 My Comm. Expires 9-26-91

Iona M. Leatherman  
 Notary Public

My Commission Expires \_\_\_\_\_